


VICINITY MAP  
NO SCALE




SOIL TEST DATA			
SOIL TESTING AND EVALUATION BY: ROBERT CRAWFORD, P.E. SOIL TESTING WITNESSED BY: RALPH H. COLE, P.L.S. DATE: NOVEMBER 24, 2015 @ 11.1' AM HIGH TIDE			
TP-1	APPROX. GRADE EL. 10.2	TP-2	APPROX. GRADE EL. 8.9
EL. 9.8	A HORIZON SAND & ROOTS 10YR 3/2	EL. 8.6	A HORIZON SAND & ROOTS 10YR 3/2
EL. 1.1	C HORIZON FINE SAND 2.5Y 5/3	EL. -0.1	C HORIZON FINE SAND 2.5Y 5/3
WEeping OBSERVED: 99" MOTTling OBSERVED: NONE PERC. RATE: <2 MPI @ 32-48" ESHGW: 99" (EL. 1.95)		WEeping OBSERVED: 88" MOTTling OBSERVED: NONE PERC. RATE: NONE ESHGW: 88" (EL. 1.57)	

SOIL TEST DATA			
SOIL TESTING AND EVALUATION BY: GREGORY J. MORSE, S.E. #2906 SOIL TESTING WITNESSED BY: RALPH H. COLE, P.L.S. DATE: MARCH 10, 2021			
TP-1A	APPROX. GRADE EL. 11.4	TP-2A	APPROX. GRADE EL. 9.0
EL. 10.4	FILL/OVERWASH	EL. 6.7	FILL/OVERWASH
EL. 3.2	C HORIZON MEDIUM SAND 2.5Y 5/4	EL. -1.0	C HORIZON MEDIUM SAND 2.5Y 5/4
WEeping OBSERVED: NONE MOTTling OBSERVED: NONE PERC. RATE: <2 MPI @ 24-42" ESHGW: NONE		WEeping OBSERVED: NONE MOTTling OBSERVED: NONE PERC. RATE: <2 MPI @ 24-42" ESHGW: NONE	



PROPOSED FLOOR PLAN  
NOT TO SCALE



SCHEDULE OF ELEVATIONS

1. PIPE INV. AT SLAB = 8.75 MINIMUM (TO CONNECT TO PILE)	6. INV. OF PIPE AT INFILTRATION CHAMBER = 7.55 (MATCH EXISTING)
2. INV. OF PIPE AT SEPTIC TANK INLET = 8.50	7. BOTTOM OF INFILTRATION CHAMBER = 6.95 (MATCH EXISTING)
3. INV. OF PIPE AT SEPTIC TANK OUTLET = 8.25	8. TOP OF CHAMBER (BREAKOUT) = 8.03 (MATCH EXISTING)
4. INV. OF PIPE AT DIST. BOX INLET = 7.88 (MATCH EXISTING)	9. FINISHED GRADE OVER SEPTIC TANK = 10.3 (MIN.) - 12.5 (MAX.)
5. INV. OF PIPE AT DIST. BOX OUTLET = 7.70 (MATCH EXISTING)	10. FINISHED GRADE OVER LEACHING FACILITY = MATCH EXISTING

## GENERAL NOTES

- SEPTIC SYSTEM INSTALLATION CONTRACTORS SHALL BE LICENSED BY THE BOARD OF HEALTH AND MUST COMPLY WITH ALL REQUIREMENTS OF THE BOARD OF HEALTH DISPOSAL WORKS CONSTRUCTION PERMIT AND ANY CONDITIONS, IF ISSUED BY THE CONSERVATION COMMISSION.
- ALL CONSTRUCTION MUST COMPLY WITH TITLE 5 OF THE STATE ENVIRONMENTAL CODE 310 CMR 15 & THE ANY LOCAL BOARD OF HEALTH SUPPLEMENTAL REGULATIONS.
- THERE SHALL BE NO CHANGES MADE IN THIS PLAN WITHOUT THE WRITTEN PERMISSION OF THE BOARD OF HEALTH AND DESIGN ENGINEER.
- ANY CHANGE IN SITE CONDITIONS, DISCREPANCIES, ERRORS OR OMISSIONS SHALL BE BROUGHT TO THE ATTENTION OF MORSE ENGINEERING PRIOR TO THE COMMENCEMENT OF WORK.
- THIS PLAN HAS BEEN PREPARED IN ACCORDANCE WITH TITLE 5 (310 CMR 15) AND THE LOCAL BOARD OF HEALTH REQUIREMENTS TO THE FULLEST EXTENT PRACTICABLE. NO GUARANTEE TO THE SYSTEMS PERFORMANCE IS EXPRESSED OR IMPLIED.
- SOIL TEST DATA SHOWN IS LIMITED TO THE CONDITIONS EXISTING AT THE SUBJECT TEST PIT LOCATION ONLY. IF DIFFERENT SOIL CONDITIONS ARE FOUND IN THE AREA OF THE PROPOSED SOIL ABSORPTION SYSTEM THEY SHALL BE BROUGHT TO THE ATTENTION OF MORSE ENGINEERING IMMEDIATELY.
- THE CONTRACTOR SHALL NOTIFY DIGSAFE PRIOR TO ANY EXCAVATION AT THE SUBJECT PROPERTY. IT IS SPECIFICALLY CAUTIONED THAT THE SUBSURFACE UTILITIES SHOWN ARE APPROXIMATE ONLY AND HAVE BEEN COMPILED FROM AVAILABLE RECORDS AND OBSERVABLE SITE FEATURES. UTILITIES OTHER THAN THOSE SHOWN MAY BE PRESENT AT THIS LOCATION.
- THIS PLAN HAS BEEN PREPARED SPECIFICALLY AS A SEPTIC SYSTEM DESIGN AND IS NOT TO BE USED TO ESTABLISH PROPERTY LINES OR BUILDING SETBACKS. PROPERTY LINES AND BUILDING LOCATIONS ARE GRAPHIC ONLY, PROPERTY LINES NOT HAVING BEEN VERIFIED. NO REPRESENTATION OR CERTIFICATION AS TO THE ACCURACY OF THOSE SHOWN IS IMPLIED.

## CONSTRUCTION NOTES



- CONTRACTOR SHALL COORDINATE INSPECTION TIMES WITH THE LOCAL BOARD OF HEALTH AND DESIGN ENGINEER 24-HOURS IN ADVANCE OF THE FOLLOWING INSPECTIONS:
  - AFTER EXCAVATION OF ALL UNSUITABLE MATERIAL FROM SOIL ABSORPTION AREA.
  - PRIOR TO COVERING THE CONSTRUCTED SYSTEM.
  - AFTER SYSTEM BACKFILL AND FINAL GRADING.
- ALL CONSTRUCTION MUST COMPLY WITH TITLE 5 OF THE STATE ENVIRONMENTAL CODE 310 CMR 15 & THE ANY LOCAL BOARD OF HEALTH SUPPLEMENTAL REGULATIONS.
- ALL TIGHT-JOINT PLUMBING SHALL BE CONSTRUCTED OF SCH. 40 PVC PIPE WITH CLEANED AND CEMENTED FITTINGS, UNLESS OTHERWISE NOTED.
- ALL PRECAST/PIPE CONSTRUCTION JOINTS AND FITTINGS SHALL BE MADE WATERTIGHT BY PARING WITH PORTLAND CEMENT.
- THE CONTRACTOR SHALL PROVIDE A SIEVE ANALYSIS OF THE TITLE 5 PERC SAND UTILIZED FOR FILL TO VERIFY THAT IT MEETS THE REQUIREMENTS OF 310 CMR 15.255(3). TITLE 5 SAND FILL SHALL COMPLY WITH THE FOLLOWING:

SIEVE SIZE	PARTICLE SIZE
#4	4.75 mm
#50	0.30 mm
#100	0.15 mm
#200	0.075 mm
- THE CONTRACTOR SHALL PREVENT ANY HEAVY CONSTRUCTION MACHINERY AND/OR TRUCKS FROM DRIVING OVER THE PROPOSED SOIL ABSORPTION SYSTEM LOCATION UNTIL FINISHED GRADE IS ESTABLISHED.
- THE CONTRACTOR SHALL INSTALL MAGNETIC TAPE OVER SYSTEM PIPING & COMPONENTS
- THE DESIGN ENGINEER SHALL CERTIFY AND PREPARE AN "AS-BUILT" PLAN FOR SUBMITTAL TO THE BOARD OF HEALTH UPON SEPTIC SYSTEM COMPLETION.
- ALL DISTURBED AREAS SHALL BE RESTORED WITH 4" LOAM & SEED POST CONSTRUCTION.
- ALL SEPTIC SYSTEM COMPONENTS TO BE STAKED OUT BY PROFESSIONAL LAND SURVEYOR PRIOR TO SYSTEM INSTALLATION.


## SITE NOTES

- LOCUS DOES NOT LIE WITHIN A DEP DESIGNATED ZONE II OR ZONE A RESOURCE AREA.
- ALL KNOWN WETLANDS WITHIN 100 FEET OF THE PROPOSED SEWAGE SYSTEM ARE SHOWN.
- PROPERTY LINE DATA WAS OBTAINED FROM RECORDED DEED (46363-306) AND RECORDED PLANS ON FILE AT THE PLYMOUTH COUNTY REGISTRY OF DEEDS.
- THERE WERE NO ACTIVE/POTABLE WELLS OBSERVED WITHIN 100' OF THE PROPOSED SYSTEM.
- LOCUS LIES IN FEMA ZONE "VE (16)", "VE (15)", AND "AE (13)" AS SHOWN ON FEMA COMMUNITY MAY PANEL 25021C 0256E DATED NOVEMBER 4, 2016. ZONE "X" IS NOT A SPECIAL FLOOD HAZARD AREA.

## \*INSTALLER TO BE INFILTRATOR CERTIFIED\*

		PREPARED BY:	
			
PROJECT:		DESIGN: PGG	
142 HUMAROCK BEACH (ASSESSOR'S PARCELS 71-4-2 & 71-4-13F) HUMAROCK, MASSACHUSETTS		CHECK: GJM	
APPLICANT:		JOB NO: 20-413	
GREGORY P. & LISA M. DECONSILII		DATE: 6/3/2021	
PLAN TITLE:		REV:	
SEPTIC & SITE PLAN		SHEET: 1	



## STAKED STRAW WATTLE DETAIL



## PLANTING NOTE:


DISTURBED EXISTING VEGETATED AREAS TO BE RESTORED WITH AMERICAN BEACHGRASS AS SPECIFIED BELOW:

- PLANT BY HAND 2 CULMS OF AMERICAN BEACHGRASS PER HOLE. EACH HOLE SHOULD BE DUG TO AT LEAST 8 INCHES DEEP.
- SPACING OF THE HOLES SHOULD BE 18 INCHES ON CENTER.
- COMPACT THE SAND AROUND THE PLANTED CULMS.
- LIGHTLY FERTILIZE THE AREA WITH A SLOW RELEASE NITROGEN FERTILIZER SUCH AS OSMOCOTE.
- PLANTING CAN BE CONDUCTED BETWEEN OCTOBER 15TH AND APRIL 15TH.



BENCHMARK  
REBAR & CAP  
EL. = 9.84  
NAVD88 DATUM

## EXISTING 1,500 GAL. SEPTIC TANK DETAIL



- THE SEPTIC TANK INLET & OUTLET COVERS SHALL BE EXTENDED TO FINISHED GRADE & EQUIPPED WITH 20" DIA. CAST IRON FRAME & COVERS.
- ALL PIPE CONNECTION AND CONSTRUCTION JOINTS SHALL BE SEALED WITH HYDRAULIC CEMENT.
- SEPTIC TANK SHALL BE INSTALLED ON A LEVEL 6" CRUSHED STONE BASE.
- EXISTING ZABEL A100 FILTER SHOULD BE CLEANED & INSPECTED. INSTALLER TO PROVIDE NEW ZABEL A100 FILTER IF NECESSARY.

## DESIGN DATA

- BUILDING TYPE: SINGLE FAMILY DWELLING
- NO. OF BEDROOMS: 4 (EXISTING) 6 (PROPOSED)
- DESIGN FLOW: 6 x 110 GPD/BEDROOM = 660 GPD (GALLONS PER DAY)
- DESIGN PERCOLATION RATE: <2 MPI (TP-1 & TP-2A)
- GARBAGE DISPOSAL: NO
- SEPTIC TANK DESIGN REQUIREMENT: 200% DESIGN FLOW  
660 X 2 = 1,320 GAL. (RE-USE EXISTING 1,500 GALLON SEPTIC TANK)
- LEACH AREA REQUIREMENTS GALLONS/SQ. FT.  
BOTTOM: 0.74 GAL./S.F. SIDE: 0.74 GAL./S.F.
- TOTAL LEACH AREA REQUIRED:  
TITLE 5: 660 GPD / (0.74 GPD/S.F.) = 892 S.F.  
PROVIDED: 6 ROWS OF 6  
EFFECTIVE AREA: (45 CHAMBERS x 5.00' L x 4.80 S.F./L.F.) = 1,080 S.F.  
CAPACITY = 1,080 S.F. x 0.74 GPD/S.F. = 799.2 GPD  
\*EFFECTIVE AREA PER GENERAL USE CERTIFICATION ISSUED BY DEP.  
RESERVE AREA CALCULATIONS  
PERCOLATION RATE: <2 MPI (TP-1 & TP-1A)  
LOADING RATE: 0.74 GAL./S.F.  
REQUIRED AREA: 660 GPD / 0.74 GPD/S.F. = 892  
PROVIDED AREA: 20' x 45' = 900 S.F.