GENERAL NOTES

- 1. NOTIFY DIG SAFE AT 888-344-7233 TO ARRANGE FOR MARKING OUT EXISTING UNDERGROUND UTILITIES AT LEAST 72 HOURS IN ADVANCE OF EXCAVATION AT ANY GIVEN LOCATION. NOTIFY THE TOWN DEPARTMENT OF PUBLIC WORKS (DPW) FOR MARKING OUT EXISTING TOWN OWNED UTILITIES. THE DPW OFFICE PHONE NUMBER IS 781-545-8732. UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR BE ALLOWED TO START ANY KIND OF EXCAVATION WORK PRIOR TO HIS OBTAINING ALL THE NECESSARY INFORMATION REGARDING THE LOCATION OF UNDERGROUND UTILITIES AT THE SITES.
- 2. THE EXISTENCE OF UTILITIES AND APPURTENANCES AS SHOWN ON THESE DRAWINGS ARE FOR REFERENCE ONLY, AND THE EXACT SIZE, TYPE, LOCATION AND ELEVATION SHALL BE THOROUGHLY INVESTIGATED BY THE CONTRACTOR PRIOR TO THE START OF CONSTRUCTION. FIELD MEASURE TO VERIFY EXISTING AND CONTRACT INTERFACE DIMENSIONS, LOCATIONS, AND OTHER CONDITIONS. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGE WHICH MIGHT BE OCCASIONED BY FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UTILITIES.
- 3. BASE MAPPING AND CONTOURS SHOWN ARE BASED ON MASSGIS DATA
- 4. THE VERTICAL DATUM SHOWN HEREON IS THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD-88).
- 5. NO WORK SHALL OCCUR WITHIN WETLAND RESOURCE AREAS UNLESS NECESSARY PERMITS ARE OBTAINED.
- 6. MINIMUM PIPE COVER SHALL BE 4'-6' AS MEASURED FROM THE UNDERSIDE OF THE PAVEMENT, UNLESS OTHERWISE SHOWN ON THE DRAWINGS OR DIRECTED IN THE FIELD BY THE OWNER'S PROJECT REPRESENTATIVE.
- 7. HORIZONTAL AND VERTICAL LOCATION OF WORK MAY BE MODIFIED TO FIT EXISTING FIELD CONDITIONS UPON APPROVAL OF THE ENGINEER OR OWNER.
- 8. PERFORM ALL EXCAVATION SO THAT UNDERGROUND UTILITIES OR STRUCTURES ARE NOT DAMAGED. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE INCURRED DURING EXCAVATION OPERATIONS. REPAIR ANY EXISTING PIPE OR UTILITY DAMAGED DURING CONSTRUCTION AT NO ADDITIONAL COST TO THE OWNER.
- 9. SHORE UTILITY TRENCHES WHERE FIELD CONDITIONS DICTATE AND/OR WHERE REQUIRED BY LOCAL, STATE AND FEDERAL HEALTH AND SAFETY CODES.
- 10. TAKE NECESSARY MEASURES AND PROVIDE CONTINUOUS BARRIERS OF SUFFICIENT TYPE, SIZE, AND STRENGTH TO PREVENT ACCESS TO ALL WORK AND STAGING AREAS AT THE COMPLETION OF EACH DAYS WORK.
- 11. STORE FUEL, OIL, PAINT, OR OTHER HAZARDOUS MATERIALS IN A SECONDARY CONTAINER AND REMOVE FROM THE SITE TO A LOCKED INDOOR AREA WITH AN IMPERVIOUS FLOOR DURING NON-WORK HOURS.
- 12. PROVIDE A SUPPLY OF ABSORBENT SPILL RESPONSE MATERIALS, SUCH AS BOOMS, BLANKETS, AND OIL ABSORBENT MATERIALS AT THE CONSTRUCTION SITE AT ALL TIMES TO CLEAN UP POTENTIAL SPILLS OF HAZARDOUS MATERIALS. IMMEDIATELY REPORT SPILLS OF HAZARDOUS MATERIALS TO MASSDEP AT 888-304-1133 AND THE COMMUNITY WHERE THE WORK IS OCCURRING.
- 13. REGRADE ALL UNPAVED AREAS DISTURBED BY THE WORK TO ORIGINAL CONTOURS OR PROPOSED CONTOURS AS REQUIRED BY THE DRAWINGS. LOAM AND SEED ALL UNPAVED AREAS DISTURBED BY THE WORK.
- 14. PROVIDE ACCESS FOR EMERGENCY VEHICLES AT ALL TIMES.
- 15. SUPPORT AND MAINTAIN ALL EXISTING UTILITIES AND STRUCTURES DURING CONSTRUCTION, IF REMOVAL OR RESTORATION OF ANY PART OF THE UTILITY IS NECESSARY, IT SHALL BE DONE ONLY WITH THE APPROVAL OF THE OWNER'S PROJECT REPRESENTATIVE, AND SHALL BE DONE IN ACCORDANCE WITH STANDARDS OF THE COMMUNITY WHERE WORK IS BEING PERFORMED AND THE STANDARDS OF THE UTILITY OWNER. NO SEPARATE PAYMENT WILL BE MADE FOR THIS WORK AND THE COST OF THIS WORK SHALL BE INCLUDED UNDER THE PRICES BID FOR THE VARIOUS ITEMS OF WORK
- 16. COMPOST FILTER TUBES AND EROSION CONTROL MEASURES SHALL BE PROVIDED AS SHOWN ON THE DRAWINGS, MAINTAINED, AND REPLACED AS NECESSARY DURING THE PROJECT.
- 17. BOLD TEXT AND LINES INDICATE PROPOSED WORK.

ELECTRIC

EACH

- 18. LIGHT TEXT AND LINES INDICATE APPROXIMATE EXISTING CONDITIONS.
- 19. REPAIR/REPLACE PAVED SURFACES DISTURBED BY THE WORK IN-KIND, UNLESS NOTED OTHERWISE.
- 20. STREET LINES AND PROPERTY LINES AS SHOWN ON THESE DRAWINGS ARE APPROXIMATE ONLY.
- 21. NOTIFY THE OWNER'S PROJECT REPRESENTATIVE OF ANY EXISTING UTILITY DISCOVERED DURING THE WORK THAT IS NOT SHOWN ON THE DRAWINGS.
- 22. NO EXCAVATION SHALL OCCUR ON THE LANDFILL SITE OR WITHIN 150 FEET OF THE LANDFILL CAP SYSTEM.
- 23. CONTRACTOR SHALL PROVIDE TEMPORARY FENCE 50-FEET EACH SIDE OF OPEN EXCAVATIONS AS SPECIFIED IN SECTION 01560.
- 24. CONTRACTOR SHALL PROVIDE CONTROLLED DENSITY FILL AT UTILITY CROSSING LOCATIONS AS DIRECTED BY THE
- 25. A TIGHE & BOND WETLAND SCIENTIST DELINEATED WETLAND RESOURCES AREA BOUNDARIES ON APRIL 7, 2021. THE DELINEATION INCLUDED INLAND BANK, MEAN HIGH TIDE (MHT) LINE, AND COASTAL DUNE. THE LIMITS OF WETLAND RESOURCE AREAS WERE LOCATED USING GLOBAL POSITIONING SYSTEMS (GPS) FOR DEPICTION ON THE PROJECT PLANS.
- 26. THE LIMIT OF LAND SUBJECT TO COASTAL STORM FLOWAGE (LSCSF) DEPICTED AT ELEVATION 16 FEET (NAVD88) BASED ON THE FEMA FLOOD INSURANCE RATE MAP PANEL NUMBER 25023C0136K (EFFECTIVE 11/4/2016).

EROSION CONTROL NOTES

- 1. ALL EROSION CONTROL MEASURES SHOWN, SPECIFIED AND REQUIRED BY THE ENGINEER SHALL BE INSTALLED PRIOR TO ANY CONSTRUCTION OR IMMEDIATELY UPON REQUEST. MAINTAIN ALL SUCH CONTROL MEASURES UNTIL FINAL SURFACE TREATMENTS ARE IN PLACE AND/OR UNTIL PERMANENT VEGETATION IS
- 2. PRIOR TO STARTING WORK, CLEARLY STAKE WORK LIMIT LINE(S). DO NOT DISTURB VEGETATION AND TOPSOIL BEYOND THE PROPOSED LIMIT LINE(S). COORDINATE WITH THE ENGINEER THE LOCATIONS FOR THE TEMPORARY STOCKPILING OF TOPSOIL DURING CONSTRUCTION.
- ANY SEDIMENT TRACKED ONTO PAVED PUBLIC RIGHT-OF-WAYS BY VEHICLES LEAVING THE PROJECT SITE SHALL BE SWEPT AWAY AT THE END OF EACH DAY.
- 4. UTILIZE ADDITIONAL CONTROL MEASURES DURING THE CONSTRUCTION PERIOD WHEN APPLICABLE.
- ALL CATCH BASINS SHALL BE PROTECTED WITH A SILT SACK, HAY BALE RING, SILT FENCE OR BLOCK AND STONE INLET PROTECTION THROUGHOUT THE CONSTRUCTION PERIOD AND UNTIL ALL DISTURBED AREAS ARE THOROUGHLY STABILIZED.
- 6. ALL DRAINAGE STRUCTURES SHALL BE PERIODICALLY INSPECTED BY THE CONTRACTOR AND CLEANED TO PREVENT THE BUILD-UP OF SILT.
- DISPOSE OF SEDIMENT REMOVED FROM CONTROL STRUCTURES OFF-SITE.
- 8. INSPECT AND MAINTAIN CONTROL MEASURES THROUGHOUT THE CONSTRUCTION PERIOD. INSPECT AFTER EACH RAINSTORM AND DURING MAJOR STORM EVENTS TO DETERMINE ALL SEDIMENTATION AND EROSION CONTROL MEASURES ARE ADEQUATELY IN PLACE AND EFFECTIVE.
- 9. UTILIZE APPROVED METHODS/MATERIALS FOR PREVENTING THE BLOWING AND MOVEMENT OF DUST FROM EXPOSED SOIL SURFACES ONTO ADJACENT PROPERTIES AND SITE AREAS.
- 10. MAINTAIN AN ADDITIONAL SUPPLY OF EROSION CONTROL MEASURES ON-SITE FOR EMERGENCY REPAIRS.
- 11. EROSION CONTROL BLANKETS SHALL BE INSTALLED ON SLOPES 3:1 OR GREATER IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS.
- 12. SIDE SLOPES, SHOULDER AREAS AND DISTURBED VEGETATED AREAS, TO BE A MAXIMUM GRADE OF 2:1, COMPACTED, STABILIZED, LOAMED AND SEEDED AS SHOWN ON PLANS. ALL SIDE SLOPES SHALL BE IMMEDIATELY FINE GRADED AND SEEDED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
- 13. DEWATER AS NECESSARY TO KEEP CONSTRUCTION AREAS FREE OF WATER. DISCHARGE WATER FROM DEWATERING TO APPROPRIATE UPLAND LOCATION WITHOUT SEDIMENTATION.
- 14. ALL SILT-LADEN WATER MUST BE SETTLED OR FILTERED TO REMOVE SEDIMENTS PRIOR TO RELEASE IN A SEDIMENTATION OR FILTER BAG LOCATED DOWNGRADIENT OF THE DEWATERED AREA.
- 15. PLACE EROSION AND SEDIMENTATION CONTROLS ALONG THE DOWNHILL SIDE OF ANY CONSTRUCTION RELATED (TEMPORARY) STOCKPILE OF MATERIAL. SURROUND STAGING AREAS WITH EROSION AND SEDIMENTATION CONTROLS TO LIMIT EROSION AND SEDIMENTATION, OR SECONDARY IMPACT OF WETLAND

EQUIPMENT REFUELING AND MAINTENANCE NOTES

- 1. THE WORK WILL OCCUR WITHIN A PUBLIC WATER SUPPLY AREA. ALL ACTIVITIES OF THE CONTRACTOR SHALL BE IN STRICT CONFORMANCE WITH ALL APPLICABLE REGULATIONS AND GUIDELINES REGARDING STORAGE OR USE OF FUEL PRODUCTS.
- 2. SECONDARY CONTAINMENT MUST BE PROVIDED AT ALL TIMES DURING THE REFUELING PROCESS. NO TRANSFERRING OR REFUELING WILL BE ALLOWED OUTSIDE OF SECONDARY CONTAINMENT
- 3. ANY FUEL CONTAINERS BROUGHT ONTO THE SITE SHALL INCLUDE SECONDARY CONTAINMENT AT ALL TIMES. UNDER NO CIRCUMSTANCES SHALL FUEL OR OTHER LUBRICANTS BE STORED AT THE SITE OVERNIGHT.
- 4. MAINTENANCE OF CONSTRUCTION EQUIPMENT, INCLUDING WASHING OF CONSTRUCTION EQUIPMENT, SHALL NOT BE ALLOWED ON-SITE. CONSTRUCTION EQUIPMENT SHALL BE INSPECTED DAILY TO PREVENT THE ACCIDENTAL DISCHARGE OF OIL OR FUEL ONTO THE GROUND AT THE SITE.
- 5. ABSORBENT SPILL RESPONSE MATERIAL INCLUDING OIL ABSORBENT MATS AND SPILL BOOMS SHALL BE KEPT ON SITE AT ALL TIMES FOR USE IN THE EVENT OF SPILLS OR ACCIDENTAL DISCHARGES. SORBENT MATERIALS SHALL BE USED TO THE MAXIMUM EXTENT POSSIBLE TO CONTAIN OR REMOVE ANY MATERIALS SPILLED OUTSIDE OF SECONDARY CONTAINMENT STRUCTURES. NOTIFY THE OWNER AND ENGINEER IMMEDIATELY IN THE EVENT OF SPILLS OR ACCIDENTAL DISCHARGES.
- 6. THE CONTRACTOR SHALL SUBMIT A VEHICLE AND EQUIPMENT FUELING AND MAINTENANCE PLAN FOR THE PROJECT. THE CONTRACTOR SHALL ENSURE THAT ALL WORKERS ON SITE ARE FAMILIAR WITH THE PLAN AND THEIR RESPONSIBILITIES RELATIVE TO THE REFUELING AND MAINTENANCE OF EQUIPMENT AND THE STEPS NECESSARY IN THE EVENT OF SPILLS OR ACCIDENTAL DISCHARGES.

REDUCER

REINFORCING

WATER GATE

WATER MAIN

WETLAND FLAG


WATER SUPPLY

PROPOSED













SECTION REFERENCE LETTER DRAWING WHERE SECTION IS

LEGEND

ABOVEGROUND BACKWASH WATER

UNDERGROUND BACKWASH WATER

UNDERGROUND WATER MAIN

OUTFALL DISCHARGE PIPE

UNDERGROUND ELECTRIC

OVERHEAD ELECTRIC

EDGE OF DIRT ROAD

CHAIN LINK FENCE

LIMIT OF INLAND BANK

LIMIT OF COASTAL DUNE

COASTAL STORM FLOWAGE

50-FOOT BUFFER ZONE

100-FOOT BUFFER ZONE

200-FOOT RIVERFRONT AREA

SEDIMENTATION AND EROSION CONTROL

MEAN HIGH TIDE LINE

LAND SUBJECT TO

MAJOR CONTOUR

MINOR CONTOUR

ACCESS COVER

STORM MANHOLE

WATER MANHOLE

TELEPHONE BOX

UTILITY POLE

LIGHT POLE

STREET SIGN

TREE OR SHRUB

BUILDING/STRUCTURE

SOIL BORING LOCATION

SHOWN OR TAKEN

HYDRANT

VALVE

CATCH BASIN

TREELINE

UNDERGROUND STORM DRAIN

EDGE OF PAVEMENT (NO CURB)

EDGE OF PAVEMENT (WITH CURB)

DETAIL REFERENCE NUMBER DRAWING WHERE DETAIL IS SHOWN OR TAKEN

EQUIPMENT, STRUCTURES, PIPING, AND/OR CONDUITS TO BE DEMOLISHED

RIPRAP

EXISTING

 \Box TEL

 \bigcirc B-1



PERMIT **DRAWINGS MAY 2021**

Well 18B Water **Treatment Plant Modifications**

Town of Scituate

Scituate, Massachusetts

	5/24/2021	PERMIT DRAWING
	3/17/2021	CONSTRUCTION SET
K	DATE	DESCRIPTION
JECT NO:		S5001-029A
E:		02/24/2021
S5001-029A-G-002.dwg		
WN BY:		GNM
CKED BY:		CJG
ROVED BY:		1NM

GENERAL NOTES, ABBREVIATIONS, AND

SCALE:

G-002

LEGEND

	ABBREVIATIONS
ECB	EROSION CONTROL BLANKET

ABW AFD AFF ALUM APA APPROX AST		EF EFFL EL ELEC ELEV EQ	ELEVATION ELECTRIC OR ELECTRICAL
ATS AV	AUTOMATIC TRANSFER SWITCH AIR VALVE	EW EXIST.	EACH WAY EXISTING
BC BFP BIT. BLDG BOR B/FTG BTM B/WALL BR	BOTTOM OF FOOTING BOTTOM	FC FD FIN. FLEX FLG FLR FM FT FTG	FOOT CANDLE FLOOR DRAIN FINISH OR FINISHED FLEXIBLE FLANGE FLOOR FLOW METER FOOT OR FEET FOOTING
BV C CB CDX	BALL VALVE OR BUTTERFLY VALVE CONDUIT CATCH BASIN EXTERIOR GRADE PLYWOOD WITH ONE SIDE RATED A `C' GRADE & THE	GA GALV GFI GR GRAV GRND	GAUGE GALVANIZED GROUND FAULT CIRCUIT INTERRUPTER GRADE GRAVEL GROUND
CI CJ	OTHER SIDE RATED A `D' GRADE CAST IRON CONSTRUCTION JOINT	GRTG GV	GRATING GATE VALVE
© CO CONC CONT CU	CENTERLINE CLEAN OUT CONCRETE CONTINUOUS COPPER	HDPE HORIZ HP H.P. HSE	HIGH DENSITY POLYETHYLENE HORIZONTAL HORSEPOWER HIGH POINT HOUSE
DEMO DI DIA, Ø	DEMOLITION DUCTILE IRON DIAMETER	HSS HVAC HYD	HOLLOW STRUCTURAL SECTION HEATING, VENTILATING & AIR CONDITIONING HYDRANT
DISCH DR DWG	DISCHARGE DRAIN OR DRIVE DRAWING	ID IN INSTR	INSIDE DIAMETER INCH OR INCHES INSTRUMENT OR INSTRUMENTATION
F	FLECTRIC	1110111	THO INCIDENT ON THO INCIDENTALION

INSUL

INSULATION

JOINT REM REMOVE REQ'D REQUIRED KILOWATT RET RETAIN POUND RO SAN **ROUGH OPENING** LINEAL FEET **SANITARY** LONG SCH SCHEDULE LIGHT POLE SD STORM DRAIN LOW POINT SHT SHEET LAMINATED VENEER LUMBER SIM **SIMILAR** MAGNETIC SURVEY NAIL SLV SLEEVE SEWER MANHOLE SMH MAXIMUM SPEC SPECIFICATION MOTOR CONTROL CENTER MANUFACTURER SPK SURVEY SPIKE MANHOLE SOUARE MINIMUM STAINLESS STEEL **MISCELLANEOUS** STD STANDARD MECHANICAL JOINT STL STEEL MASONRY OPENING **STRUC** STRUCTURE OR STRUCTURAL MOISTURE RESISTANT T&B TOP & BOTTOM MANUAL TRANSFER SWITCH TBM TEMPORARY BENCHMARK MANUAL ON UNIFORM TEL TELEPHONE TRAFFIC CONTROL DEVICES TEMP **TEMPORARY** NORMALLY CLOSED T/FTG TOP OF FOOTING T/STL TOP OF STEEL T/WALL TOP OF WALL NATIONAL ELECTRICAL TP TELEPHONE POLE MANUFACTURERS ASSOCIATION TYP TYPICAL NOT TO SCALE UNDERGROUND BACKWASH WATER **NORMALLY OPEN** UNLESS NOTED OTHERWISE NUMBER UTILITY POLE ON CENTER OUTLET CONTROL STRUCTURE **VENT OUTSIDE DIAMETER VOLTS** OVERHEAD ELECTRIC **VERT** VERTICAL OUTFALL DISCHARGE PIPE V.I.F. VERIFY IN FIELD WATER PROPERTY LINE

WG

WF

WM

RED

REINF

N.T.S. WITH

PREMOLDED JOINT FILLER

POLYVINYL CHLORIDE

PUBLIC WATER

INT

INV

KW

L.P.

LVL

MAG

MAX

MCC

MFR

MH

MIN

MJ

M.O.

M.R.

NO.

PVC

MTS

MISC

INTERIOR

INVERT





PERMIT DRAWINGS MAY 2021

Well 18B
Water
Treatment
Plant
Modifications

Town of Scituate

Scituate, Massachusetts

1	5/24/2021	PERMIT DRAWING	
0	3/17/2021	CONSTRUCTION SET	
MARK	DATE	DESCRIPTION	
PROJE	CT NO:	S5001-029A	
DATE:		02/24/2021	
FILE: S5001-029A-C-101-102.dwg			
DRAWI	N BY:	GNM	
CHECK	ED BY:	CJG	

PROPOSED PLAN FILTER BACKWASH DISPOSAL 1 OF 2

APPROVED BY:

SCALE: 1" = 40'

C-101





PERMIT DRAWINGS MAY 2021

Well 18B
Water
Treatment
Plant
Modifications

Town of Scituate

Scituate, Massachusetts

1	5/24/2021	PERMIT DRAWING			
0	3/17/2021	CONSTRUCTION SET			
MARK	DATE	DESCRIPTION			
PROJE	CT NO:	S5001-029A			
DATE:		02/24/2021			
FILE: S5001-029A-C-101-102.dwg					
DRAWI	N BY:	GNM			
CHECK	ED BY:	CJG			
APPRO	VED BY:	1NM			

PROPOSED PLAN FILTER
BACKWASH DISPOSAL 2 OF 2

SCALE: 1" = 40'

C-102