



**PLANTING LEGEND**

SYMBOL	PLANT MATERIAL
(Circle with dot)	DECIDUOUS TREE
(Circle with cross)	EVERGREEN TREE
(Circle with vertical lines)	SHRUB

**SEEDING NOTES**

- SEED TO BE FRESH, CLEAN, NEW CROP SEED.
- SEEDING SHALL CONSIST OF SOIL PREPARATION, SEEDING, RAKING, ROLLING, WEEDING, WATERING AND LABOR AND MATERIALS TO SECURE ESTABLISHMENT AND ACCEPTANCE.
- IMMEDIATELY BEFORE SOWING SEED, SCARIFY GROUND OR RAKE LIGHTLY UNTIL SURFACE IS SMOOTH.
- PROVIDE WATERING AS NECESSARY FOR ACCEPTABLE ESTABLISHMENT. WATER TO MAINTAIN ADEQUATE MOISTURE IN UPPER 5-INCHES OF SOIL TO PROMOTE DEEP ROOT GROWTH. WATER IN A MANNER PROVIDING UNIFORM COVERAGE WHILE PREVENTING EROSION.
- FOLLOWING ESTABLISHMENT, MOW AS NEEDED TO MAINTAIN A HEIGHT OF 4" - 6" FOR FIRST GROWING SEASON.
- HAND SEED, BROADCAST SEED, HYDROSEED, OR DRILL SEED. FOR AREAS WITH SLOPE LESS THAN 3:1, COVER THE SEED 1/8"-1/4" DEEP BY DRAGGING WITH A SPRING-TOOTH HARROW OR FIRMLY PRESSING THE SEED INTO THE SOIL USING A CULTIPACKER.
- FOR AREAS WITH SLOPE GREATER THAN 3:1, FINAL TRACKING SHOULD BE PERPENDICULAR TO THE SLOPE TO AID IN REDUCING EROSION AND RETAINING SEED AND MOISTURE. MULCH WITH STRAW, HYDROMULCH, OR STRAW/COCONUT FIBER MATS TO PROTECT THE SEED FROM DRYING OUT OR WASHING AWAY. FOR AREAS STEEPER THAN 3:1, THE USE OF EROSION CONTROL BLANKETS OR FLEXIBLE GROWTH MEDIUM IS RECOMMENDED. WHEN USING EROSION CONTROL BLANKETS, BE SURE THEY ARE TOED IN AT THE TOP OF THE SLOPE.

**PLANTING NOTES**

- LANDSCAPE ARCHITECT TO APPROVE PLANT MATERIAL PRIOR TO DELIVERY TO SITE.
- PLANT MATERIAL SHALL CONFORM TO "THE AMERICAN STANDARD FOR NURSERY STOCK", PUBLISHED BY AMERICAN HORT.
- NO SUBSTITUTIONS OF PLANT SPECIES WITHOUT LANDSCAPE ARCHITECT'S WRITTEN APPROVAL.
- SUBSTITUTIONS OF PLANT SPECIES SHALL BE A PLANT OF EQUIVALENT OVERALL FORM, HEIGHT AND BRANCHING HABIT, FLOWER, LEAF AND FRUIT, COLOR AND TIME OF BLOOM, AS APPROVED BY LANDSCAPE ARCHITECT.
- LOCATE AND VERIFY UTILITY LINE LOCATIONS PRIOR TO STAKING AND REPORT CONFLICTS TO LANDSCAPE ARCHITECT.
- PLANTING DEMOLITION DEBRIS, GARBAGE, LUMPS OF CONCRETE, STEEL AND OTHER MATERIALS DELETERIOUS TO PLANTS' HEALTH AS DETERMINED BY LANDSCAPE ARCHITECT SHALL BE REMOVED FROM ALL PLANTING AREAS.
- NO PLANTING TO BE INSTALLED BEFORE ACCEPTANCE OF ROUGH GRADING.
- ALL PROPOSED TREE LOCATIONS SHALL BE STAKED OR LAID OUT IN THEIR APPROXIMATE LOCATION BY THE CONTRACTOR. REFER TO LAYOUT AND PLANTING SHEETS FOR LAYOUT INFORMATION. THE CONTRACTOR SHALL ADJUST THE LOCATIONS AS REQUESTED BY THE LANDSCAPE ARCHITECT TO ACCOUNT FOR SUBSURFACE UTILITIES AND OTHER FIELD CONDITIONS. FINAL LOCATIONS OF ALL PLANTS MUST BE APPROVED BY THE LANDSCAPE ARCHITECT PRIOR TO PLANTING.
- INSTALL PLANTS WITH ROOT FLARES FLUSH WITH FINISHED GRADE. IMMEDIATELY REPLANT PLANTS THAT SETTLE OUT OF PLUMB OR BELOW FINISHED GRADE.
- WATER PLANTS THOROUGHLY AFTER INSTALLATION, A MINIMUM OF TWICE WITHIN THE FIRST 24 HOURS.
- REPAIR DAMAGE DUE TO OPERATIONS INSIDE AND OUTSIDE OF LIMIT OF WORK.
- SOAK ALL PERENNIALS FOR 24 HOURS PRIOR TO INSTALLATION.



THIS DOCUMENT IS THE PROPERTY OF WOODARD & CURRAN AND ITS CLIENT. REPRODUCTION OR MODIFICATION WITHOUT WRITTEN PERMISSION IS PROHIBITED.



**ISSUED FOR PERMIT**

CLIENT INFO:  
TOWN OF SCITUATE  
MASSACHUSETTS  
453 CHIEF JUSTICE  
CUSHING HIGHWAY

STEARNS MEADOW  
DRINKING WATER  
TREATMENT PLANT

**PLANT SCHEDULE**

TREES				
SYM.	QTY.	BOTANICAL NAME	COMMON NAME	SIZE
AR	9	ACER RUBRUM	RED MAPLE	2 1/2" - 3" CAL.
AS	8	ACER SACCHARUM	SUGAR MAPLE	3" - 3 1/2" CAL.
CC	4	CERCIS CANADENSIS	EASTERN REDBUD	8' - 10' HT. MULTI-STEM
PS	21	PINUS STROBUS	EASTERN WHITE PINE	12' - 14' HT.
PR	18	PINUS RIGIDA	PITCH PINE	8' - 10' HT.
QB	4	QUERCUS BICOLOR	SWAMP OAK	2 1/2" - 3" CAL.
QR	3	QUERCUS RUBRA	RED OAK	3" - 3 1/2" CAL.

SHRUBS				
SYM.	QTY.	BOTANICAL NAME	COMMON NAME	SIZE
Ac	35	AMELANCHIER CANADENSIS	SERVICEBERRY	6'-7' HT. MULTI-STEM
Mp	34	MYRICA PENNSYLVANICA	NORTHERN BAYBERRY	3'-4' HT
Rm	43	RHODODENDRON MAXIMUM	ROSEBAY RHODODENDRON	3'-4' HT
Vc	32	VACCINIUM CORYMBOSUM	HIGHBUSH BLUEBERRY	5'-6' HT
Vd	37	VIBURNUM DENTATUM	ARROWWOOD VIBERNUM	5'-6' HT

**SEED MIXES**

	<b>LOW-MOW</b> 6lbs/ 1,000 SF	FESTUCA RUBRA FESTUCA BREVIPILA, 'BEACON' FESTUCA BREVIPILA, 'HARPOON' FESTUCA RUBRA SSP. COMMUTATA POA PRATENSIS, 'SHAMROCK' POA PRATENSIS, 'VOLT' TRIFOLIUM REPENS, 'DUTCH'	CREeping RED FESCUE HARD FESCUE, 'BEACON' HARD FESCUE, 'HARPOON' CHEWINGS FESCUE KENTUCKY BLUEGRASS, 'SHAMROCK' KENTUCKY BLUEGRASS, 'VOLT' WHITE CLOVER, 'DUTCH'
	<b>SEEDDED LAWN</b> 6lbs/ 1,000 SF	JASPER CREeping RED FESCUE VICTORY CHEWING FESCUE WARWICK HARD FESCUE LIMOUSINE KENTUCKY BLUEGRASS JEFFERSON KENTUCKY BLUEGRASS	
	<b>EROSION CONTROL</b> 1lb/ 1,250 SF	ELYMUS RIPARIUS SCHIZACHYRIUM SCOPARIUM FESTUCA RUBRA ANDROPOGON GERARDII PANICUM VIRGATUM VERNONIA NOVEBORACENSIS AGROSTIS PERENNANS BIDENS FRONDOSA EUTROCHIUM MACULATUM EUPATORIUM PERFOLIATUM SYMPHYOTRICHUM NOVAE-ANGLIA CYPERINUS JUNCUS EFFUSUS	RIVERBANK WILD RYE LITTLE BLUESTEM RED FESCUE BIG BLUESTEM SWITCH GRASS NEW YORK IRONWEED UPLAND BENTGRASS BEGGAR TICKS SPOTTED JOE PYE WEED BONESET NEW ENGLAND ASTER WOOL GRASS SOFT RUSH

NEW ENGLAND WETLAND PLANTS SEED MIX: NEW ENGLAND EROSIONS CONTROL MIX FOR DETENTION BASINS

**LANDSCAPE PLANTING PLAN**

DRAWING NO:  
**L-101**