



768 Washington Street, Route 53, Hanover, MA 02339
781-826-4205 • Fax 781-826-4440
www.northstarbailey.com

September 25, 2015

Scituate Housing Authority
791 Country Way
Scituate, MA 02060

Re: Central Park
Central Park Drive
Scituate, MA

Page 1 of 2

Window Proposal - First Floor Apartments Only

First Floor - FRONT of the Building:

Installation includes removing the vinyl siding and the old window frames from the existing window openings. Any plywood sheathing and framing members will remain intact. All new windows at Central Park will be installed as new construction type windows and will be flashed with materials and methods as described in accordance with AAMA (American Architectural Manufacturers Association) style 'B' method.

Install 36 white Harvey Classic vinyl double hung windows into the existing window openings with half screens, Energy Star glazing and between glass colonial grids. 24 of the windows have 8/8 grids and 12 windows have 4/4 grids.

Install new interior window trim as needed on the interior of the new windows.

Install Azek PVC trim on the exterior of the windows and around the perimeter of the wall sheathing where it meets the brick walls. Install new exterior vinyls siding as needed.

Windows, material and labor included.

Front of Building, First Floor, Job Price: **\$64,400.00**

Window Proposal - First Floor Apartments Only

First Floor - REAR of the Building:

Installation includes removing the vinyl siding and the old window frames from the existing window openings. Any plywood sheathing and framing members will remain intact. All new windows at Central Park will be installed as new construction type windows and will be flashed with materials and methods as described in accordance with AAMA (American Architectural Manufacturers Association) style 'B' method.

Install 33 white Harvey Classic vinyl double hung windows into the existing window openings with half screens, Energy Star glazing and between glass colonial grids.

Install new interior window trim as needed on the interior of the new windows.

Install Azek PVC trim on the exterior of the windows and around the perimeter of the wall sheathing where it meets the brick walls. Install new exterior vinyl siding as needed.

Windows, material and labor included.

Rear of Building, First Floor, Job Price: **\$66,700.00**

Total Job Cost, Front and Rear First Floor Apartment Windows at Central Park: **\$131,100.00**

All Prices Are Subject To Change After November 30, 2015